

Super House Education Foundation DPS Bareilly

Date of Issue : 20

Utkarsh Infratech Builder and Contractor,

GSTIN:- 09BXSPM6841F1ZW

Boq of Dps Bareilly Hostel(Second floor with civil & Finishing works & miscellaneous works)-Area of floor-6100 Sqft					
S.no	Description of work	Unit	QTY	Rate	Qty
1	Earth work in foundation trenches or drains for all kinds of soils (not exceeding 1.5 m in width or 10 sqm on plane) including dressing of sides ramming bottom, lift up to 1.5m, including getting out excavated soil and disposal of surplus excavated soil as directed within site with back filling	Cum	1	650	50
2	Plain Cement Concrete 1:4:8 (1 Cement, 4 Coarse sand and 8 Graded Stone 40 mm nominal size) in plinth under floor, foundatin or where required. Including consolidatin and curing etc. complete.	Cum	1	5090	41.09
3	Reinforced Cement Concrete is M-25(with Minimum cement content- 400Kg), it will be check at the time of final billing. including laying , and curing but excluding Centring , Shuttering ,reinforcement and plastering .	Cum	1	7150	136.5
4	Providing M.S Reinforcement for R.C.C work including Cutting bending, binding & Placing in positions complete.	Kg	1	76	22500
5	Centering and Shuttering upto any level including Striting, Propping etc. and removal of forms as per design and directin with good timber/ ply, steel material approved by the consultant for -	Sqm	1	330	1460
6	Brick Masonary in Super Structure using bricks of Class designation 75 in cement mortar 1:6 (1 Cement , 6 Coarse Sand) including the cost of necessary scaffolding up to any height and any floor including curing etc. complete.	Cum	1	6500	299
7	Brick masonary 115mm Thick in Superstructure using bricks of Class 75 in cement mortar 1:4 including the cost of necessary scaffolding upto any height and any floor including curing etc complete	Sqm	1	995..00	310
8	Smooth Plaster 12 to 15mm over walls upto all height and all floors ,Laid Cured including Surface preparation complete & making grooves as directed or hacking on column surface	SQm	1	342	3161
9	Prov & laying of Fine river sand for flooring	Cum	1	1050	7
10	P&L Vitrified Tiles Flooring /Wall Tilesover 20mm Cement moratr 1:4 with base rate of tile-Rs45-50/Sqft(as Directed by site incharge /Architect	SQm	1	1180	1120
11	P&L Vitrified Tiles skirting over 20mm cement moratr with base rate of tile-Rs45- 50/Sqft(as Directed by site incharge /Architect	Rmtr	1	180	450
12	Prov & fixing sal wood chaukhat for doors	Cft	1	2810	43
13	Electrical work(Each room-2 nos fan point,1 nos Ac Point(4mm wire, 2 nos ceiling lights Point, Cat-6 networking cable with camera Points and all things as per attached drawings.	Sqft	1	145	5520
14	Prov & Fixing of Plumbing work CP & Sanitary work including rainwater Pipes as per attached drawings	Sqft	1	95	5520
15	Providing and fixing 20 mm thick Sader Ali granite stone of approved quality in rises steps skirting dade pillars laid in 12mm thick (avg) Cement Mortar 1:3 mix (1 Cement 3 coarse sand) and jointed with white cement Slurry including polishing complete as per design	Sqm	1	3250	65.5
16	Providing and Fixing Sader Ali Granite Scarting	Rmtr	1	250	65
17	Providing and fixing 20 mm thick Tan Brown granite stone of approved quality in rises steps skirting dade pillars laid in 12mm thick (avg) Cement Mortar 1:3 mix (1 Cement 3 coarse sand) and jointed with white cement Slurry including polishing complete as per design	Sqm	1	3250	12

18	Drip course	Rmtr	1	200	27
19	Applying Two or more coat applied @ 1.67 ltr/10 sqm over and including Putty & Primer & Apex Paint	Sqm	1	187	3161
20	Providing POP punning with scaffolding	Sqm	1	300	244.5
21	Half round granite moulding	Rmtr	1	49	270.5
22	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. With average thickness of 120 mm and minimum thickness at khurra as 65 mm.	Sqm	1	1250	490
23	Providing and fixing MS Railing And Window Grill	Kg	1	110	500
24	Providing and Fixing Fastner 100mm	Nos	1	85	50
25	Dismantling of Brick work with Disposal including lifting & lead	Cum	1	450	25
26	Wooden Bidding on Wooden Chowkhat	Rmtr	1	400	155
27	Painting on Sal wood Chaukhats for doors.	Sqm	1	110	35
28	Providing and laying 300mm x 300mm x 25 mm thick chequered grey precast cement concrete tile of approved shape over 25mm average thick base mortar of mix 1:4 (1 cement : 4 Coarse sand) finished with flush pointing in cement mixed with pigment to match the shade of tiles in approved pattern, cutting, curing etc. complete as per design & drawings.(for Outer development work)	Sqm	1	950	20
29	Dismantling of chakaer tiles	Sqm	1	10	20
30	Providing and fixing Powder coated Aluminium Doors and windows and ventilators made out of standard aluminium section-1.5mm (JINDAL AND HINDALCO) as per design including 1.5 mm thick plain sheet glass glazing fixed with EDPM Gasket with Steel Screws, Rubber weather strips , rocol plug, gutties etc. complete as per the Architects design and as directed.	Sqm	1	4100	44
31	Providing and fixing Powder coated Aluminium Doors and windows and ventilators made out of standard aluminium section-1.5mm (JINDAL AND HINDALCO) as per design with toughen glass-5mm saint gobin glazing fixed with EDPM Gasket with Steel Screws, Rubber weather strips , rocol plug, gutties etc. complete as per the Architects design and as directed.	Sqm	1	4500	13.5
32	Dismantling of existing brickcoba with proper disposal with lifting & lead including.	Sqm	1	100	490
33	Prov & Fixing of flush doors-32mm(Green) with all necessary fittings complete	Sqm		3251	52
34	Miscellaneous work(Verified at the time of final billing)	Job	1	120000	1
35	Dismantling of existing Profile sheet with Ms Purlins with Properly stacking at site.	Job	1	4500	1
36	Fixing of Profile sheet with Ms Purlins on labour rate	Job	1	6500	1
37	Fire staircase(Back side building)				
i	Prov & Faricating with erection of MS staircase with primer	Kg	1	110	6450
ii	Fabricatio & Erection of Ms Railing with primer	Kg	1	110	740
iii	P/F of nut bolts	Kg	1	100	80
iv	P /F of fastners	Pcs	1	100	15

	v Prov & laying of enamel paint on structural steel	Ton	1	2200	7.19
	Sub total				
Note	Cement-Ultratech/Prism				
	Steel-Jsw/Tata/Jspl				
	Paint-Berger/Asian				
	Putty- JK birla/wall max				
	Brick-First class brick				
	POP-Sakarni				
	Aluminium Window-Hindalco/Tata with Tuffen glass				
	Structural steel-Sail/Tata				
	Lifting & Scaffolding is included in this rate				
	Electrical work-Wire(Havells,Polycab,KEI), & Fitting (Havells-Base model)				
	Flush door-32mm thick (Green)				
	Plumbing work (Cera or Plumber)-CP & Sanitary (PVC Pipe-6Kg,CPVC Pipe-SDR-11)Make-Supreme				
	Tiles make-Kajaria				
	Gst is extra				

)-09-2024

Amount
32500
209148
975975
1710000
481800
1943500
308450
1081062
4200
1321600
81000
118250
800400
524400
212875
16250
39000

5400
591107
73350
13254
612500
55000
2900
11250
62000
3850
19000
200
180400
60750
49000
169052
120000
4500
6500
709500
81400
8000
1500

[illegible]

**Super House Education Foundation
DPS Gomti Nagar, Lucknow**

Date of Issue : 22-05-2025

Sl.	Particulars	Unit	Total Qty.	Utkarsh Infratech Builder and Contractor	
				Rate	Amount
A.	Civil Work				
1	Earth Work				
1.1(a)	Excavation 0.00m to 1.50m with back filling	M3	0.00	-	-
2	CONCRETE WORK (PLAIN & REIN.)				
2.1	Prov. & Laying P.C.C. 1:4:8, Cement consumption-3.5 Bags/Cum.	M3	3.51	4,130.40	14,504.94
2.2	Prov. & Laying R.C.C M-20 (Mix 1:1-1/2:3), Cement consumption-7.5 Bags/Cum.				
2.2(a)	Suspended floor/slabs/coffer slab/ Beams/Column	M3	4.82	5,679.30	27,384.84
2.3	Prov. & Laying R.C.C M-20 (Mix 1:1-1/2:3) of 4" th. Precast chamber cover including lifting, shifting and fixing complete	M2	0.00	6,023.50	-
3	Prov. Centering & shuttering work / upto any ht.				
	Suspended floor/slabs/coffer slab/ Column	M2	30.60	361.41	11,059.15
4	Prov. & lay.Tor Steel Reinforcement (Deformed Bars)	MT	0.78	64,537.50	50,339.25
5	Masonry work				
5.1	Prov. & laying 1st class brick work in Super Structure upto any ht.	M3	33.34	5,335.10	1,77,861.56
5.2	Prov. & laying Half Brick masonry work in super structure upto any ht.	M2	0.00	-	-
6	Tile / Stone / Granite /Kota work				
6.1	P/L of 18-22mm th. kota stone in floor with base mortar upto desire slope	M2	42.00	1,075.63	45,176.25
6.2	P/L of 18-22mm th. Granite on floor & counter top with base mortar/Adhesive	M2	46.45	2,753.60	1,27,907.84
6.3	P/L of Cannes Crema Tile in Floor (Base Rate : 60 Rs./Sft.)	M2	0.00	-	-
6.4	Making Of Full Round Moulding On Granite	RMT	75.80	254.02	19,254.69
6.5	Making Of Half Round Moulding On Granite	RMT	12.80	141.12	1,806.36
6.6	Only Kota Floor Polish as per instruction of Site engineer	M2	0.00	-	-
6.7	P/L of 1200x600mm Onyx ivory polish in wall Tile including base mortar Make: Kajaria	M2	409.92	1,032.60	4,23,283.39
6.8	P/L of 600x600mm Haven Moka Matt in Floor Tile including base mortar Make: Kajaria	M2	186.94	1,032.60	1,93,036.11
6.9	P/L of floor Tile with chemical Adhesive	M2	60.20	1,032.60	62,163.21
6.10	P/L of Floor Tile tile including base mortar (Base Rate : 60 Rs./Sft.)	M2	0.00	-	-
6.11	P/L Of Chakkar tile work	M2	0.00	-	-
6.12	P/L of Morbat marble work	M2	27.87	2,581.50	71,948.16
7	Plaster work				
7.1	Prov. & laying 18-20 mm Th. External plaster	M2	255.32	352.81	90,078.94
7.2	Prov. & laying 18-20 mm Th. Plaster with water proofing chemical (consumption: 250ml per bag of cement)	M2	526.92	370.02	1,94,968.30
7.3	Extra For neat Coat	M2	526.92	129.08	68,012.20
7.4	Prov. & laying 12 to 15 mm Thk. plaster in cement mortar	M2	0.00	-	-
7.5	Proving & Fixing of G.I. Chicken mesh	M2	0.00	-	-
8	Paint work				
8.1	P/A of white cement Work on plaster area	M2	222.60	21.51	4,788.68
8.2	P/A of Two coat base putty work in Building area	M2	656.84	60.24	39,564.85
8.3	Prov. & laying Synthetic enamel paint on steel work	M2	1470.10	94.66	1,39,152.57
8.4	Finishing of wall with oil Bound distemper	M2	3093.19	73.14	2,26,243.85
8.5	Prov. & laying of External paint upon wall	M2	1422.35	103.26	1,46,871.86

8.6	Prov. & laying Synthetic enamel paint on steel work	KGS	110.00	4.30	473.28
9	Water proofing Work				
9.1	Prov& lay. Two Coat of EMCE FLEX-30 / Tape Crete Polymer Modified water proofing	M2	579.64	352.81	2,04,500.66
9.2	Providing & laying 125mm of brick bat coba work	M2	117.00	946.55	1,10,746.35
10	HVAC System work				
10.1	Supply of Hitachi ductable system- High Side	As per Quot.	1.00	-	-
10.2	Supply of Hitachi ductable system- Low Side	As per Quot.	1.00	-	-
10.3	providing & fixing MS platform work with primer	Kg.	3500.00	94.66	3,31,292.50
10.4	providing & fixing synthetic Enamel Paint work	Kg.	3500.00	4.30	15,058.75
11	Electrification work				
	electrification work per Toilet (At the time of final bill the bill will be verified)	Nos.	7.50	17,210.00	1,29,075.00
12	Extra Items				
12.1	Scaffolding work	M2	216.65	189.31	41,013.65
12.2	Prov & Fixing anodoised aluminium door /window work with 5mm plain glass	M2	56.28	3,355.95	1,88,872.87
12.3	partly glazed partly paneled shutter	M2	4.80	3,355.95	16,108.56
12.4	Providing & fixing of 12mm toughned glass with cluding cost of G-W connector, G-G connection & all neccesary patches complete	M2	17.60	4,732.75	83,296.40
12.5	Prov & Fixing anodoised aluminium partition work with 4.0mm ACP Sheet complete	M2	0.00	-	-
12.6	Aluminium door machine fixing work	PEC	4.00	2,151.25	8,605.00
12.7	P/F of Door Closer	PEC	3.00	1,032.60	3,097.80
12.8	P/F of MS railing complete with primer	Kg.	605.48	94.66	57,311.24
12.9	Dismantling & removing of MS shed and staking in safe place as per site in charge	M2	34.50	146.29	5,046.83
12.10	Increase the Shed height(MS)	Kg	1000.00	103.26	1,03,260.00
12.11	Providing & fixing Profile sheeting as per requirement of Site-In - Charge with complete	M2	200.45	1,075.63	2,15,603.65
12.12	Due to lack of space shifting of malwa from all the area and Shifted back side area	M3	0.00	-	-
12.13	Providing & laying None Metalic Hardener (Hardner Consumption: 3.5Kg/Sqm. & Make-Fosroc)	M2	0.00	60.24	-
12.14	Finish With Trimix Floater	M2	0.00	180.71	-
12.15	Cutting & filling polysulphite	RMT.	0.00	-	-
12.16	Epoxy grouting of 16 mm dia. Bar	nos	16.00	860.50	13,768.00
12.17	Epoxy grouting of 10 mm dia. Bar	nos	60.00	860.50	51,630.00
12.18	Epoxy grouting of filling for existing floor area	M2	37.16	129.08	4,796.54
12.19	malwa shifting from trley due to lack of space	nos	0.00	-	-
12.20	Leveling, dressing & compacting work	M2	7.02	34.42	241.75
12.21	Removing of Aluminium Partion work	M2	18.60	154.89	2,880.95
12.22	Refixing of Aluminium partition work including of repairing with screws complete	M2	18.60	258.15	4,801.59
12.23	Providing & filling & compacting malwa complete	M2	5.00	516.30	2,581.50
12.24	Dismantling of Brick work with shifting of malwa as per site incharge at ground floor	M3	89.18	258.15	23,021.57
12.25	Dismantling of RCC with shifting of malwa as per site incharge at ground floor	M3	16.97	387.23	6,571.09
12.26	Dismantling of PCC with shifting of malwa as per site incharge at ground floor	M3	0.00	387.23	-

12.27	Dismantling of tile with shifting of malwa as per site incharge at ground floor	M2	657.06	387.23	2,54,431.02
12.28	Dismantling of Granite with shifting of malwa as per site incharge at ground floor	M2	37.16	387.23	14,389.63
12.29	Dismantling of brick bat coba with shifting of malwa as per site incharge at ground fl	M2	117.00	129.08	15,101.78
12.30	Dismantling of false ceiling with shifting of malwa as per site incharge at ground fl	M2	36.79	94.66	3,482.29
12.31	providing & fixing of 12.5mm th. Gypsum false ceiling as per site incharge	M2	36.79	1,110.05	40,837.78
12.32	Due to lack Of Space Storage of soil with JCB Machine	Hour	0.00	-	-
12.33	Supply of manpower		0.00	-	-
12.33 (a)	Meson	NOS	0.00	-	-
12.33 (b)	Labour	Nos	0.00	-	-
12.34	Dismantling of Old palla & chaukhat removing with proper stacking on site as per sit	Nos	18.00	516.30	9,293.40
12.35	Removing of MS Ventilators	Nos	2.00	172.10	344.20
12.36	Repairing of Old door frame with shutter if required and mentioned the job which have been done to work on door	Nos	18.00	430.25	7,744.50
12.37	Providing & fixing Acoustic Paneling work & false ceiling work complete	As per Quot.	1.00	-	-
12.38	Shifting of Malwa by tractor trolly with including loading, unloading as per site in charge complete	Nos	133.00	688.40	91,557.20
	Total Amount (Civil Work)				41,96,244.34
B.	Plumbing Work				
1	Providing & Fixing Indian Type water Closet suit Comparising white vitreas orissa pan 580mm(23") Long with integrated squatting plate and raised footrest with P trap all Providing & Fixing materials for viteous ware including cutting wall/floor and making Good Surfaces etc.complete	Each	10.00	2,151.25	21,512.50
1a	Providing & Providing & Fixing PVC Cistern (10Ltr) etc Complete	Each	10.00	774.45	7,744.50
1b	Providing & Fixing European WC one piece floor mounted with all necessary arrangements	Each	4.00	6,453.75	25,815.00
1.2	Providing & Providing & Fixing of Wash Basin				
a	Below Counter	Each	8.00	2,151.25	17,210.00
b	Wall mounted	Each	0.00	-	-
C	Upper Counter	Each	0.00	-	-
1.3	Providing & Providing & Fixing of Urinal				
a	one flat back	Each	8.00	2,151.25	17,210.00
b	Two flat Back	Each	0.00	-	-
1.4	Providing & Providing & Fixing Urinal Partion	Each	8.00	2,151.25	17,210.00
1.5	Providing & Providing & Fixing of 32mm Waste Coupling	Each	16.00	129.08	2,065.20
1.6	Providing & Providing & Fixing Concealed Stop Cock	Each	0.00	-	-
1.7	Providing & Providing & Fixing Health faucet	Each	4.00	774.45	3,097.80
1.8	Providing & Providing & Fixing OH Shower	Each	0.00	-	-
1.9	Providing & Providing & Fixing of Diverter (single lever)	Each	0.00	-	-
1.20	Providing & Providing & Fixing Glass mirror				
a	900x900mm	Each	0.00	-	-
b	900x1500mm	Each	4.00	774.45	3,097.80
1.21	Providing & Providing & Fixing 2 Way Bib Cock	Each	4.00	1,548.90	6,195.60
1.22	Providing & Providing & Fixing of Coat Hook	Each	0.00	-	-
1.23	Providing & Providing & Fixing SS jali	Each	34.00	94.66	3,218.27
1.24	Providing & Providing & Fixing of Soap Dish	Each	4.00	129.08	516.30
1.25	Providing & Providing & Fixing of Paper Holder	Each	4.00	301.18	1,204.70
1.26	Providing & Providing & Fixing of Bottle trap	Each	16.00	946.55	15,144.80
1.27	Providing & Providing & Fixing of UpVC gullay trap	Each	0.00	-	-
1.28	Providing & Providing & Fixing of UpVC Floor trap	Each	0.00	-	-
1.29	Providing & Providing & Fixing of Taps				

1.30	Providing & Providing & Fixing of Long Body	Each	10.00	920.74	9,207.35
1.31	Providing & Providing & Fixing of Short Body	Each	0.00	-	-
1.32	Providing & Providing & Fixing of pillar cock	Each	8.00	1,462.85	11,702.80
1.33	Providing & Providing & Fixing of Angle valve	Each	34.00	731.43	24,868.45
1.34	Providing & Providing & Fixing of Urinal Spreader	Each	8.00	731.43	225.00
1.35	Providing & Providing & Fixing of lead connection pipe	Each	34.00	94.66	3,218.27
2.0	Providing & Providing & Fixing approved quality P.V.C soil, rain and waste pipes including junctions bends, off set cleaning eyes, Y junctions, tees Cows etc. of heavy quality fixed with heavy quality M.S holder including cutting the walls/ flooring/ core cutting as necessary and restoring the disturbed portions to avoid shrinkage of concrete Grout or equivalent shall be used as an adhesive in concrete).				
A	75 mm dia.	Rmt	0.00	-	-
B	90mm dia	Rmt	0.00	-	-
C	110 mm.dia.	Rmt	0.00	-	-
D	160 mm dia	Rmt	0.00	-	-
2.1	Providing & Providing & Fixing approved quality P.V.C soil, rain and waste pipes including junctions bends, off set cleaning eyes, Y junctions, tees Cows etc. including cutting of RCC road, excavation, pcc& rcc casting, shuttering necessary and restoring the disturbed portions to avoid shrinkage of concrete Grout or equivalent shall be used as an adhesive in concrete).				
A	75 mm dia.	Rmt	0.00	-	-
B	110 mm.dia.	Rmt	400.00	989.58	3,95,830.00
C	160 mm dia	Rmt	0.00	-	-
D	200 mm dia	Rmt	0.00	-	-
3	Construction of Rectangular/ CONICAL masonry inspection chamber of In brick in C.M 1:5 Mix 225 mm thick walls all round over a bed of 150 mm thick PCC of 1:4:8 Mix with 40 mm graded stone jelly and plastered in C.M 1:3 inside top and outside to smooth finish, forming, benching and channeling and rendered with C.M (1:2) as required at bottom and fitted with RCC Cover including earth work excavation of required depth and width in trenches, refilling the trench with excavation earth watering consolidation etc. complete depth up to 1.00 meter. with chamber cover complete				
a	Construction of 900x900 Man Hole	Nos	0.00	6,453.75	-
b	Construction of 900x1500 Man Hole	Nos	0.00	-	-
c	Construction of 900x2000 Man Hole	Nos	0.00	-	-
d	Construction of 600x600 Man Hole	Nos	0.00	-	-
e	Construction of 600x1500 Man Hole	Nos	0.00	-	-
f	Construction of 600x2000 Man Hole	Nos	0.00	-	-
4	Providing & Fixing and jointing CPVC pipes with fitting such as tees, bends providing bore holes, ferrule connections, sockets, elbows, extension pieces, reducers, unions check nuts etc. complete approved make, including chase cutting in brick work/R.C.C threading earth work excavation of required depth and width in trenches in all kind of laterite rock, refilling the trench with excavated earth, watering, consolidating bailing out water from the trench, providing necessary shorting, shuttering for the trenches required dispose off surplus earth or rack cart away the dismantled materials etc. providing brick pillar supports wherever necessary, providing clamps suspenders etc. wherever necessary, and reinstating the walls/ floor to original conditions. including pressure testing etc. complete.				
A	12mm	Rmt	0.00	-	-
B	20mm	Rmt	130.00	344.20	44,746.00
C	25mm	Rmt	120.00	413.04	49,564.80
D	32mm	Rmt	0.00	-	-
E	40mm	Rmt	36.00	473.28	17,037.90
F	50mm with scaffolding Complete	Rmt	0.00	-	-
G	65mm	Rmt	0.00	-	-
H	80mm	Rmt	0.00	-	-
I	100mm	RMT	0.00	-	-

5	Providing & Providing & Fixing Ball Valves with T Connection				
A	16 mm	Nos	0.00	-	-
B	20 mm	Nos	8.00	387.23	3,097.80
C	25 mm	Nos	0.00	-	-
D	32 mm	Nos	0.00	-	-
E	40 mm	Nos	2.00	1,548.90	3,097.80
F	50 mm	Nos	0.00	-	-
G	65 mm	Nos	0.00	-	-
H	100 mm	Nos	0.00	-	-
6	Extra Item				
6.1	C I Jali				
a	200 mm	Nos	0.00	-	-
b	150 mm	Nos	0.00	-	-
6.2	Tank Nipple				
a	100mm	Nos	0.00	-	-
b	65mm	Nos	0.00	-	-
c	Providing & Providing & Fixing of Pump	Nos	0.00	-	-
d		JOB	0.00	-	-
6.3	Dismantling of PVC Pipe	RMT	0.00	-	-
6.4	Dismantling of GI pipe	RMT	0.00	-	-
6.5	opening of 20mm union	PEC	0.00	-	-
6.6	Urinal partition , wash basin ,urinal removing	PEC	0.00	-	-
6.7	Removing of Angle Valve & Pillar coak	PEC	0.00	-	-
7	Miscellanoous Civil Work(Verify as per site)	Nos	10000.00	1.00	1,00,000.00
	Total Amount (Plumbing Work)				8,03,838.64
	Total Amount (Civil+Plumbing Work)				50,00,082.98

Note: GST will be Extra as per Gov. Norms

Make & Specification

Follow the materials specification & Make if not mentioned in above Item descriptions

C.P Fittings : Commercial CERA, HINDWARE

CPVC pipe & fittings : 6.5 Kg. pressure, Make- SUPREME

PVC pipe & fittings : SDR-11 , Make- SUPREME

Tor. Steel : JSW, TATA & SAIL

Structural Steel : SAIL

Tile : KAJARIA

Cement : Ultatech & ACC

Water Proofing Chemical : EMCE Flex 300

Paint & Primer : ASIAN PAINTS & BURGER

Elec. Cable & wire : POLYCAB & HAVELS

Elec. Switch, Scoket & plate : HAVELS Commercial

Putty : BIRLA

Brick : 1st Class

Copper Cable : KEI, HAVELS